



NOTES:

1. GC to verify all required masonry rough openings. typ.
2. 4" lally column, thicken slab as required for load bearing typ.
3. Continuous poured concrete footing as required.
4. Stairs to first floor:
14risers @ 7.4" +/- vif
13 treads @ 9 1/2" + 1" nose
total rise = 8'-7 3/4" +/- vif
total run = 10'-3 1/2"
5. 8" sonotube w/bell footing to frost depth min. typ.
6. 2 x 6 PT @ 24" O.C. Deck joists above. typ.
7. 3 - 2 x 8 PT Deck beam above
8. 1 - 2 x 8 PT Deck beam above
9. 2 - 2 x 8 PT Deck beam above

REVISIONS:	
△	Relocated Deck Sonotubes

FOUNDATION/BASEMENT PLAN

LOG HOME FOR AMY & ANDREW BOYDEN
9903 PROJECT #
6/6/99 DATE
1/4" = 1'-0" SCALE
FOUNDATION PLAN
A3.1
SHEET