



WINDOW SCHEDULE		(PELLA Proline Windows)				
#	Type	Model #	R.O. (W)	R.O. (H)	Qty	Remarks
A	Mulled Double Hung	PLCDH 3757-VV	6' - 2 3/4"	4' - 9 3/4"	3	Two Wide Unit
B	Double Hung	PLCDH 3347	2' - 9 3/4"	3' - 11 3/4"	3	
C	Double Hung	PLCDH 2553	2' - 1 3/4"	4' - 5 3/4"	2	
D	Double Hung	PLCDH 2941	2' - 5 3/4"	3' - 5 3/4"	1	
E	Mulled Double Hung	PLCDH 2953-VV	4' - 10 3/4"	4' - 5 3/4"	2	Two Wide Unit
F	Double Hung	PLCDH 3735	3' - 1 3/4"	2' - 11 3/4"	1	
G	Double Hung	PLCDH 3757	3' - 1 3/4"	4' - 9 3/4"	6	Egress Unit
H	Fixed Companion Unit	PLCDH 4759	3' - 11 3/4"	4' - 11 3/4"	1	See Alt.
I	Double Hung	PLCDH 2559	2' - 1 3/4"	4' - 11 3/4"	2	See Alt.
J	Hopper or Awn	VIF	VIF	VIF	3	Utility Unit as req.
K	Fixed	Proline Fixed Shape	Unit W = 2'-0"	Unit H = 6'-8"	2	
L	Fixed	Proline Fixed Shape	Unit W = 2'-0"	Unit H = 5'-1"	1	
Alt. (H-I)	45° Bay Window Unit	PLCDH 29-53-2959	8'-4 3/8"	5' - 1 1/4"	1	Frame as Req. VIF

EXTERIOR DOOR SCHEDULE						
#	Type	Manuf.	Model #	R.O. (W)	R.O. (H)	Qty
1	Inswing w/Sidelites	As Req.				1
2	Inswing French	Pella Proline	PLCIF 7281	6' - 0"	6' - 8 5/8"	1
3	Six Panel Inswing	As Req.				1
4	Four Panel Sliding	Pella Designer	DSCSC 11782	9' - 8 7/8"	6' - 8 5/8"	1

GENERAL NOTES:
 1. Model #'s and Rough Openings as listed are for "Pella Proline Windows" Unless otherwise noted. Alternate window Manufacturers may be substituted upon owners approval.
 2. Egress windows as listed in schedule must meet the minimum clear opening requirements of 20" wide and 5.7 sq.ft. clear opening.
 3. GC to verify all window options (Glazing, Grilles, Color, Trim, ect.) with Owner.

FRONT ELEVATION

LOG HOME FOR NICK & KAREN PIAZZA PROJECT
1/3/00 DATE
1/4" = 1'-0" SCALE
A2.1
FRONT ELEVATION SHEET