



WINDOW SCHEDULE (ALL UNITS LISTED AS PELLA PROLINE)						Notes:
#	Type	Unit # /Series	Rough Opening	Qty	Comments	
A	2-WIDE CASEMENT	2571 - 2W	4'-2 3/4" x 5'-11 3/4"	4		TYPICAL: - VERIFY ALL GLAZING, FRAME AND GRILL OPTIONS FOR ALL UNITS LISTED OWNER MAY MAKE SUBSTITUTIONS AS NEEDED PROVIDE ALTERNATE PRICING
B	CASEMENT	2571	2'-1 3/4" x 5'-11 3/4"	2	LEFT - HAND HINGING	
C	CASEMENT	2571	2'-1 3/4" x 5'-11 3/4"	2	RIGHT - HAND HINGING	
D	2-WIDE FIXED	4771 - 2W	7'-10 3/4" x 5'-11 3/4"	2		
E	2-WIDE FIXED TRAP.		7'-10 3/4" x 6'-10 3/4"	2	SEE DETAIL ON DWG. A2.2	
F	HORIZ. SLIDING	5941	4'-11 3/4" x 3'-5 3/4"	2	VERIFY CLOSEST STANDARD SIZE	
alt. F	2-WIDE CASEMENT	2941	4'-10 3/4" x 3'-5 3/4"			
G	FIXED	7141	5'-11 3/4" x 3'-5 3/4"	1		
H	CASEMENT	2947	2'-5 3/4" x 3'-11 3/4"	1	(EGRESS) RIGHT - HAND HINGING	
I	CASEMENT	2947	2'-5 3/4" x 3'-11 3/4"	1	(EGRESS) LEFT - HAND HINGING	
EXTERIOR DOOR SCHEDULE						OWNER TO SELECT MANUF. & STYLE OWNER TO SELECT MANUF. & STYLE OWNER TO SELECT MANUF. & STYLE
1	INSWING ENTRY DOOR	RIGHT HAND ED	68 1/2" X 82 1/2"	1	2 - 14" SIDELIGHTS	
2	SLIDING PATIO DOOR	7281 XO	6'-0" x 6'-8 5/8"	2		
3	INSWING FRENCH DOOR	3781	3'-1 1/4" x 6'-8 5/8"	1	LEFT - HANDED	
4	INSUL. EXTERIOR DOOR	2 WIDE	75 1/4" X 82 1/2"	1		
5	INSUL. OVERHEAD DOOR	9'-0" X 8'-0"	VIF	2		

FRONT ELEVATION

Tree House
 Timber Frame &
 Log Homes
 (802) 464 - 5125
John R. Guminak
 Drafting & Design
 Services
 (802) 464-5423

TISO RESIDENCE PROJECT	5/28/02	A2.1
	DATE	
	1/4" = 1'-0"	SCALE